

OFFICE OF THE NAGPUR MUNICIPAL CORPORATION



[GARDEN AND TREE AUTHORITY DEPARTMENT]

Email id : gardendepnmc@gmail.com

P.B.X. No. 84 Civil Lines,
Mahanagarpalika Marg
Nagpur-1

No : NMC/GRDN/OWL/2023-24/ 10205

Date : 07/06/2023

E- QUOTATION NOTICE

E- Quotations NMC Invites Rate For NON CSR ITEM For the Folling Work. These Quotation Can be Submitted by the Entrepreneur Working in this sector of their authorized **Dealer/Manufacturer/Artists** Quotation Shall be Submitted office before Date :- 12/07/2023 Time 15:00 Pm of the Garden Superintendent (Garden Dept) 6th Floor "C" Wing, NMC Civil Line Nagpur.

NON CSR ITEM

Sr. No	Item Description	Qty	Unit	Rate
1	Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "Gond couple with Dog" at Point 1 between Sitabuldi Square to Jhansi Rani Square.	1	No	
2	Rice powdering Gond ladies (2)" at Point 2	1	No	
3	Gond ladies with Jewellery (2)" at Point 3	1	No	
4	Bamboo basket weaving Gond Lady" at Point 4	1	No	
5	2 Gond Ladies grinding grain" at Point 5	1	No	
6	2 Gond Ladies in Paddy field" at Point 6	1	No	
7	Gond couple Painting House" at Point 7	1	No	
8	Gond Ladies (2) Vending at Market" at Point 8	1	No	
9	Gond Lady with 2 Kids on Bamboo Machan" at Point 9	1	No	
10	Gond Ladies gathering from forest" at Point 10	1	No	
11	Gond couple cooking" at Point 11	1	No	
12	Mother with Child in cradle" at Point 12	1	No	
13	Rituals with 2 standing and 2 Sitting figures and tree" at Point 13	1	No	
14	Gond Couple Marriage" at Point 14	1	No	
15	Gond married couple with Tree of Life" at Point 15	1	No	
16	Gond Male and Female Headdress" at Point 16	1	No	
17	Dance with Stills and Sticks 2 figures" at Point 17	1	No	
18	Flute and Dhol players 2 figures" at Point 18	1	No	
19	2 Femaels Dancing with 1 male Nagada player figures" at Point 19	1	No	
20	Ceremonial Dance 2 male figures" at Point 20	1	No	
21	Budhadev Symbol" at Point 21	1	No	
22	Totem Pole with Deity " at Point 22	1	No	
23	Three headed Deity " at Point 23	1	No	
24	Totem Poles (2) Carver " at Point 24	1	No	
25	Gond Depictions of Animals and Birds." Peacock " at Point 25	1	No	
26	Animals and Birds." Fish " at Point 26	1	No	
27	Animals and Birds."Ox and Bird " at Point 27	1	No	
28	Animals and Birds." Flying Elephant " at Point 28	1	No	
29	Animals and Birds." Tiger " at Point 29	1	No	
30	Animals and Birds." Deer " at Point 29	1	No	

Note:

- 1) These rates will be used for deciding rates/ Estimation purpose only.
- 2) Right to Reject any or all Quotation without Issusing any reason is reserved by the municipal G.S. NMC Nagpur.
- 3) Rates Quoted Shall be Excluding GST.
- 4) Rates Shall be quoted for single unit.
- 6) Detailed Description of Items Are Available in the Office of the Garden Superintendent (Garden Dept) NMC Civil Line Opp Vidhan Bhavan Nagpur.
- 7) Last Date Of Submission, 12/07/2023 up to 15.00 Pm
- 8) Opening Date 13/07/2023 From 16.00 Pm
- 9) Details of item with plicterial representation are also available on the Website of NMC Nagpur <https://www.nmcnagpur.gov.in/quotation-notices/gardendepnmc/noncsrfile>

Garden Superintendent

Nagpur Municipal Corporation, Nagpur

Adv No:

Date:-

OFFICE OF THE NAGPUR MUNICIPAL CORPORATION



[GARDEN AND TREE AUTHORITY DEPARTMENT]

Email id : gardendpt.nmc@gmail.com

P.B.X. No. 84 Civil Lines,
Mahanagarpalika Marg
Nagpur-1


No : NMC/GRDN/OWL/2023-24/ 10205

Date : 07/06/2023

E- QUOTATION NOTICE


E- Quotations NMC Invites Rate For NON CSR ITEM For the Folling Work. These Quotation Can be Submitted by the Entrepreneur Working in this sector of their authorized **Dealer/Manufacturer/Artists** Quotation Shall be Submitted office before Date :- 12/07/2023 Time 15:00 Pm of the Garden Superintendent (Garden Dept) 6th Floor "C" Wing, NMC Civil Line Nagpur.


NON CSR ITEM

Sr. No	Photo	Item Description	Qty	Unit	Rate
1		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "Gond couple with Dog" at Point 1 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1'Height. Sculpture size : Male Figure : 6' Height with actual proportion in Width. Female Figure : 5'.6" Height with actual proportaion in Width. Dog Figure: 25" Height with actual proportion in Width Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
2		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "Rice powdering Gond ladies(2)" at Point 2 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, , installation of all sculptures on brickwork + RCC pedestal of 7'Length and 6' Width and 1' Height. Sculpture size : Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
3		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "Gond ladies with Jewellery(2)" at Point 3 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, , installation of all sculptures on brickwork + RCC pedestal of 5'Length and 5' Width and 1' Height. Sculpture size : Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
4		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "Bamboo basket weaving Gond Lady" at Point 4 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, , installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size : Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	

5		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "2 Gond Ladies grinding grain" at Point 5 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint , , installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size : Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
6		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. "2 Gond Ladies in Paddy field" at Point 6 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint , , installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size : Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
7		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. " Gond couple Painting House" at Point 7 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint , , installation of all sculptures on brickwork + RCC pedestal of 10'Length and 4' Width and 1' Height. Sculpture size : Male Figure : 6' Height with actual proportion in Width. Female Figures : 5'.6" Height with actual proportion in Width. House Size: 8' Height x 10' Length and 3' Width Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
8		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. " Gond Ladies (2) Vending at Market" at Point 8 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 4' Width and 1' Height. Sculpture size :Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
9		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. " Gond Lady with 2 Kids on Bamboo Machan" at Point 9 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures Machan of 6'Length and 4' Width and 4'Height and 3' Height. Sculpture size :Female Figures : 5'.6" Height with actual proportion in Width. Kid1 Figure: 3' height with actual proportion in Width Kid2 Figure :2' height with actual proportion in Width Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
10		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. " Gond Ladies gathering from forest" at Point 10 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	

11		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. " Gond couple cooking" at Point 11 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Male Figure : 6' Height with actual proportaion in Width. Female Figures : 5'.6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. <u>Fixing with inner Iron support structure</u>	1	No	
12		Providing & Fixing FRP sculptures based on Daily Life of Gond Tribals. " Mother with Child in cradle" at Point 12 between Sitabuldi Square to Jhansi Rani Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Female Figures : 5'.6" Height with actual proportion in Width. Child Figure: 2' Height with actual proportion in width Additional Props as seen in images, as per actual proportions. <u>Fixing with inner Iron support structure</u>	1	No	
13		Providing & Fixing FRP sculptures based on Weddings of Gond Tribals. " Rituals with 2 standing and 2 Sitting figures and tree" at Point 13 between Jhansi Rani Square to Panchasheel Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size : Female Figures : 5'.6" Height with actual proportion in Width. Child Figures: 3' Height with actual proportion in width. Tree Figure: 8'Height with actual proportion in width. Additional Props as seen in images, as per actual proportions. <u>Fixing with inner Iron support structure</u>	1	No	
14		Providing & Fixing FRP sculptures based on Weddings of Gond Tribals. " Gond Couple Marriage" at Point 14 between Jhansi Rani Square to Panchasheel Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 7'Length and 7' Width and 2' Height. . Sculpture size :Female Figures : 5'.6" Height with actual proportion in Width. Male Figure : 6' Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. <u>Fixing with inner Iron support structure</u>	1	No	
15		Providing & Fixing FRP sculptures based on Weddings of Gond Tribals. " Gond married couple with Tree of Life" at Point 15 between Jhansi Rani Square to Panchasheel Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Female Figures : 5'.6" Height with actual proportion in Width. Male Figure : 6' Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. <u>Fixing with inner Iron support structure</u>	1	No	
16		Providing & Fixing FRP sculptures based on Weddings of Gond Tribals. " Gond Male and Female Headdress" at Point 16 between Jhansi Rani Square to Panchasheel Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of both sculptures on RCC indepaendant pillars of 8" x 8" and 24"Height . Sculpture size :Male Headdress : 5' Height x 3' Width. Female Headdress : 5' Height x 3' Width. Additional Props as seen in images, as per actual proportions. <u>Fixing with inner Iron support structure</u>	1	No	

17		Providing & Fixing FRP sculptures based on Dance of Gond Tribals. "Dance with Stills and Sticks 2 figures" at Point 17 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Male Figure : 7'5" Height with stills and actual proportion in Width. Female Figures : 5'6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
18		Providing & Fixing FRP sculptures based on Dance of Gond Tribals. "Flute and Dhol players 2 figures" at Point 18 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Male Figures : 6' Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
19		Providing & Fixing FRP sculptures based on Dance of Gond Tribals. "2 Femaels Dancing with 1 male Nagada player figures" at Point 19 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Male Figure : 6' Height with actual proportion in Width. Female Figures : 5'6" Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
20		Providing & Fixing FRP sculptures based on Dance of Gond Tribals. "Ceremonial Dance 2 male figures" at Point 20 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size :Male Figure : 6' Height with actual proportion in Width. Additional Props as seen in images, as per actual proportions. Fixing with inner Iron support structure	1	No	
21		Providing & Fixing FRP sculptures based on Gond Deities. "Budhadev Symbol" at Point 21 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC pillar pedestal of 8" x 8" and 36" height Sculpture size : 5' Height x 3' Width. Fixing with inner Iron support structure	1	No	
22		Providing & Fixing FRP sculptures based on Gond Deities. "Totem Pole with Deity " at Point 22 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 6'Length and 4' Width and 1' Height. Sculpture size : Totem Pole : 8' Height x 18" Width. Deity : 4' Height x 2' Width. Fixing with inner Iron support structure	1	No	

23		Providing & Fixing FRP sculptures based on Gond Deities. " Three headed Deity " at Point 23 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 5'Length and 5' Width . Sculpture size : Deity : 6' Height and Width as per proportion. Fixing with inner Iron support structure	1	No	
24		Providing & Fixing FRP sculptures based on Gond Deities. " Totem Poles (2) Carver " at Point 24 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on brickwork + RCC pedestal of 10'Length and 6' Width and 1' Height. Sculpture size : Male figure: 6'Height and Width as per proportion. Totem Poles : 8' Height and Width as per proportion. Fixing with inner Iron support structure	1	No	
25		Providing & Fixing FRP sculptures based on Gond Depictions of Animals and Birds." Peacock " at Point 25 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC pillar of 8" x 8" with 36" Height . Sculpture size : Peacock figure: 5'Height and Width as per proportion. Fixing with inner Iron support structure	1	No	
26		Providing & Fixing FRP sculptures based on Gond Depictions of Animals and Birds." Fish " at Point 26 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC pillar pedestal of 8" x 8" with 36" Height . Sculpture size : Fish figure: 5'Height and Width as per proportion. Fixing with inner Iron support structure	1	No	
27		Providing & Fixing FRP sculptures based on Gond Depictions of Animals and Birds."Ox and Bird " at Point 27 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC conical pillar pedestal of 24" x 24" with 36" Height . Sculpture size : Figure: 5'Height and Width as per proportion. Fixing with inner Iron support structure	1	No	
28		Providing & Fixing FRP sculptures based on Gond Depictions of Animals and Birds." Flying Elephant " at Point 28 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC pillar of 8" x 8" with 36" Height . Sculpture size : Figure: 5'Height and 12' Width . <u>Fixing with inner Iron support structure</u>	1	No	
29		Providing & Fixing FRP sculptures based on Gond Depictions of Animals and Birds." Tiger " at Point 29 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC pillar of 8" x 8" with 36" Height . Sculpture size : Figure: 4'Height and 8' Width . <u>Fixing with inner Iron support structure</u>	1	No	
30		Providing & Fixing FRP sculptures based on Gond Depictions of Animals and Birds." Deer " at Point 29 between Panchasheel Square to Lokmat Square. FRP 6 mm thickness ,matt finish with exterior waterproof acrylic paint, installation of all sculptures on RCC pillar of 8" x 8" with 36" Height . Sculpture size : Figure: 5'Height and 8' Width . Fixing with inner Iron support structure	1	No	

Note:

- 1) These rates will be used for deciding rates/ Estimation purpose only.
- 2) Right to Reject any or all Quotation without issuing any reason is reserved by the municipal G.S. NMC Nagpur.
- 3) Rates Quoted Shall be Excluding GST.
- 4) Rates Shall be quoted for single unit.
- 6) Detailed Description of Items Are Available in the Office of the Garden Superintendent (Garden Dept) NMC Nagpur.
- 7) Last Date Of Submission, 12/07/2023 up to 15.00 Pm
- 8) Opening Date 13/07/2023 From 16.00 Pm
- 9) Details of item with pictorial representation are also available on the Website of NMC Nagpur <https://www.nmcnagpur.gov.in/quotation-notices/gardendep/nonsrfile>

Adv No:

Date:-

Garden Superintendent
Nagpur Municipal Corporation, Nagpur